


PLAN
SCALE N.T.S



SECTION B
SCALE 1:250

NOTES:

1. WHEN THE DEPTH FROM THE UNDERSIDE OF SLAB TO TOP OF COVER IS LESS THAN 0.75m OR WHERE MULTIPLE PIPES ARE INSTALLED, THE JUNCTION PIT IS TO BE OF BRICK CONSTRUCTION ABOVE THE CONVERSION SLAB
2. CONCRETE TO BE 20mm NOMINAL AGGREGATE AND HAVE A MINIMUM STRENGTH AT 28 DAYS OF:
 PRECAST UNIT: 40MPa
 INSITU BASE: 20MPa
3. COMPACT SUBGRADE TO 95% M.M.D.D. BEFORE PLACING BASE
4. IN HIGH GROUNDWATER AREAS THE BASE AND PIT MUST BE SEALED
5. STEP IRONS TO BE INSTALLED IN ACCORDANCE WITH THE CITY OF GOSNELLS' REQUIREMENTS
6. FOR GENERAL CONSTRUCTION DETAILS OF CAST-IN SITU CONCRETE BASE REFER TO DRAWING NO. ES-19-1 (ADAPT ACCORDINGLY)

AMENDMENTS	REVISION	DATE	DESCRIPTION	BY	CHECKED	APPROVED
3	21/10/2021	MISSING REFERENCE POINT RESTORED	MJJ	AT	SA	
2	4/2/2015	LAYERS & DRAWING NO'S UPDATED	SA	MB	MB	
1	22/02/11	UPDATE TITLE BLOCK	GL	MB	MB	

GENERAL NOTES

1. THIS DRAWINGS ALWAYS REMAINS THE PROPERTY OF THE CITY OF GOSNELLS AND MUST NOT BE RETAINED OR REPRODUCED WITHOUT PERMISSION
2. IN THE ABSENCE OF THE APPROVED SIGNATURE (ie MANAGER TECHNICAL SERVICES) THIS DRAWING SHALL BE TREATED AS PRELIMINARY
3. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE

CITY OF GOSNELLS

2120 Albany Highway Gosnells 6110
 PO Box 662, GOSNELLS 6990
 WESTERN AUSTRALIA

Telephone 08 9397 3000
 Facsimile 08 9397 3333
 Online www.gosnells.wa.gov.au

STANDARD DRAWING		
BRICK JUNCTION PIT		
DESIGN	DRAWN	DRAWING A3
SCALE AS SHOWN	CHECKED MB	DATE 10/11/09

STANDARD DRAWING NUMBER	ES-19-9
MANAGER TECHNICAL SERVICES	M.BOTTE 4/2/15
	M. BOTTE